

44 Linus 5x4 v.1

ID	Name	Height	Width	Length	Qty	3D Front Axonometry	
FBE-1	Floor bearer	44	60	3800	9		■
A01	Wall A	135	44	2727	8		┆
A02	Wall A	135	44	663	22		┆
A03	Wall A	135	44	754	7		┆
B01	Wall B	135	44	5000	15		┆
C01	Wall C	68	44	4000	1		┆
C02	Wall C	135	44	4000	7		┆
C03	Wall C	135	44	1345	12		┆
C04	Wall C	135	44	1645	1		┆
C05	Wall C	135	44	1945	1		┆
C06	Wall C	135	44	5000	1		┆
D01	Wall D	68	44	4000	1		┆
D02	Wall D	135	44	4000	12		┆
D03	Wall D	135	44	4300	1		┆
D04	Wall D	135	44	4600	1		┆
D05	Wall D	135	44	5000	1		┆
Extra01	Wall Extra	135	44	5000	1		┆
GBL01	Gable ends	135	44	5000	2		┆
GBL02	Gable ends	135	44	4192	2		┆
GBL03	Gable ends	135	44	3144	2		┆
GBL04	Gable ends	135	44	2096	2		┆
GBL05	Gable ends	135	44	1048	2		┆
PR-1	Purlin	140	68	5000	4		┆
PR-2	Purlin	140	68	5000	1		┆
RB-1	Roof board	19	135/110/87	2737	75/93/117		-
FB-1	Floor board	19	135/110/87	4707	29/35/44		-
TRIM	Trim	40	19		21 m'		
WBA	Windboard A	90	19	2856	4		┆
WBB	Windboard B	70	19	5000	2		┆
WBC	Windboard C	19	40	2856	4		-
WBD	Windboard D	25	30	5000	2		-
WB-RMB	Rhombus	200	19	19	2		◆
STRM-BR	Storm braces	47	28	1980	4		┆
Installation kit for assembly							

N01	Nail	---	2,5	40	900 (500+200+200)		
S-01	Screw	---	3	40	100		
S-03	Screw	---	5	100	10		
S-04	Screw	---	5	120	15 (10+5)		
SB	Washer	---	M10	---	8		
	Screw	---	8	50	8		