






68 Pergola-Kipa							
ID	Layer	Height	Width	Length	Qty	3D Front Axonometry	
FBE-1	Floor bearer	68	60	3800	2		
FBE-2	Floor bearer	68	60	3680	9		
001	Logs	68	68	568	2		
002	Logs	135	68	568	24		
003	Logs	135	68	818	2		
004	Logs	135	68	1068	4		
005	Logs	135	68	4000	24		
006	Logs	68	68	4000	1		
007	Logs	135	68	468	36		
008	Logs	135	68	300	6		
009	Logs	135	68	918	2		
010	Logs	135	68	768	2		
011	Logs	135	68	1418	2		
012	Logs	135	68	4700	1		
013	Logs	135	68	4700	1		
A01	Logs skliautai	135	68	4000	1		
A02	Logs skliautai	135	68	3141	1		
A03	Logs skliautai	135	68	2096	1		
A04	Logs skliautai	135	68	1050	1		
B01	Logs skliautai	135	68	4000	1		
B02	Logs skliautai	135	68	3141	1		

B03	Logs skliautai	135	68	2096	1		
B04	Logs skliautai	135	68	1050	1		
Extra	Logs	135	68	4000	1		
PR-1	Purlin	140	68	4700	1		
PR-2	Purlin	140	68	4700	2		
RB	Roof board	19	135/110/87	2221	71/91/109		
TB-1	Terrace board	28	115	3727	26		
TB-2	Terrace board	28	115	3659	8		
RL	Railing	90	19	3065	2		
WBA	Windboard	113	19	2300	4		
WBB	Windboard	70	19	4700	2		
WBC	Windboard	19	40	2300	4		
WBD	Windboard	25	30	4700	2		
WB-RMB	Rhombus	200	19	19	2		
Instalation kit for assembly							
N01	Nail	---	2,5	40	350 (200+50*3)		
S-01	Screw	---	3	40	100		
T-01	Screw	---	5	60	250		
S-03	Screw	---	5	100	10		
S-04	Screw	---	5	120	30 (10*3)		