



28 Toronto 3x3 S26295

ID	Layer	Height	Width	Length	Qty	3D Front Axonometry	
FBE-1	Floor bearer	28	60	2800	2		
FBE-2	Floor bearer	28	60	2680	6		
A01	Log wall	135	28	783	14		
A02	Log wall	135	28	783	14		
A03	Log wall	135	28	2975	1		
A04	Log wall	135	28	733	3		
A05	Log wall	135	28	733	3		
A06	Log wall	135	28	3200	1		
B01	Log wall	135	28	2975	14		
B02	Log wall	135	28	3200	1		
C01	Log wall	68	28	2975	1		
C02	Log wall	135	28	2975	14		
C03	Log GBL	135	28	2975	1		
C04	Log GBL	135	28	2501	1		
C05	Log GBL	135	28	1783	1		
C06	Log GBL	135	28	1065	1		
C07	Log GBL	68	28	347	1		

D01	Log wall	68	28	2975	1		
D02	Log wall	135	28	2975	14		
D03	Log GBL	135	28	2975	1		
D04	Log GBL	135	28	2501	1		
D05	Log GBL	135	28	1783	1		
D06	Log GBL	135	28	1065	1		
D07	Log GBL	68	28	347	1		
Extra01	Log wall	135	28	2975	1		
PR-1	Purlin	140	44	3200	3		
RB-1	Roof board	19	135/110/87	3358	25/30/38		
FB-1	Floor board	19	135/110/87	2739	21/26/33		
TRIM	Trim	22	28		12 m		
WBA	Windboard	90	19	3596	2		
WBB	Windboard	70	19	3200	2		
WBC	Windboard	19	40	3596	2		
WBD	Windboard	25	30	3200	2		
STRM-BR	Storm braces	47	28	1980	4		
KIT	Installation kit	---	---	---	1		