



28 Ariadne 2,2x2,2

ID	Layer	Height	Width	Length	Qty	3D Front Axonometry	
FBE-1	Floor bearer	28	60	2000	5		
A01	Logs wall	135	28	395	14		
A02	Logs wall	135	28	395	14		
A03	Logs GBL	135	28	2200	1		
A04	Logs GBL	135	28	1665	1		
A05	Logs GBL	135	28	1110	1		
A06	Logs GBL	135	28	555	1		
B01	Logs wall	135	28	2200	14		
B02	Logs GBL	135	28	2200	1		
B03	Logs GBL	135	28	1665	1		
B04	Logs GBL	135	28	1110	1		
B05	Logs GBL	135	28	555	1		
C01	Logs wall	68	28	2200	1		
C02	Logs wall	135	28	2200	12		
C03	Logs wall	135	28	2300	1		
C04	Logs wall	135	28	2500	1		

D01	Logs wall	68	28	2200	1		
D02	Logs wall	135	28	2200	12		
D03	Logs wall	135	28	2300	1		
D04	Logs wall	135	28	2500	1		
Extra01	Logs wall	135	28	2500	1		
PR	Purlin	140	44	2500	1		
RB	Roof board	19	135/110/87	1390	38/46/59		
FB	Floor board	19	135/110/87	1939	16/19/23		
TRIM	Trim	22	28		9 m		
STRM-BR	Storm braces	47	28	1980	4		
WBA	Windboard	90	19	1509	4		
WBB	Windboard	70	19	2500	2		
WBC	Windboard	19	40	1509	4		
WBD	Windboard	25	30	2500	2		
WB-RMB	Rhombus	200	19	19	2		
Installation kit for assembly							
N01	Nail	---	2,5	40	250		
S-01	Screw	---	3	40	50		

S-03	Screw	---	5	100	5		
S-04	Screw	---	5	120	10		
SB	Washer	---	M10	---	4		
	Screw	---	8	50	4		